

WAYNE Precharged Well Air Tank System

CONSTRUCTION

- Corrosion Resistant All Cast Iron Motor Housing
- 1 in. NPT Discharge
- Reliable Thermoplastic Impeller for Maximum Water Flow
- Dual Voltage 120 V/240 V and a 30/50 Pressure Switch Included


BENEFITS


- This pump is assembled in the USA to deliver dependable performance that lasts for years.
- Quality and Reliability. Warrantied.
- Pump Part #59501-WYN2














WAYNE PRECHARGED WELL AIR TANK SYSTEM

MODEL: SWS50-8.5FX. 1/2 HP

PUMP SNAPSHOT

- **HP** 1/2 HP
- Construction Cast Iron
- Switch Type N/A
- Motor 120/240V Split Phase Oil-Filled
- Impeller Centrifugal
- Intake 1 1/4 in. NPT
- Discharge 1 in.
- Submersible N/A
- **UPC** 040066218889
- Power Cord Wire in Field

PERFORMANCE

SWS50-8.5FX-1/2 HP - Max Flow 711 GPH: 674 GPH @ 5ft.

FLOW RATE: GALLONS PER HOUR

SWS50-8.5FX - 1/2 HP	GPH @ 5'			
Gal/Hr @0 Max Flow 711	674 @ 30 PSI	638 @ 30 PSI	601 @ 30 PSI	565 @ 30 PSI

3 YEAR LIMITED WARRANTY

- Assembled in USA with Foreign and Domestic Parts
- 30/50 Pressure Switch Included



PERFORMANCE: SWS50									
MODEL	PSI	MAX FLOW	5'	10'	15'	20'	25'		
	30	711	674	638	601	565	529		
SWS50	40	543	506	470	433	397	361		
	50	375	338	302	265	229	193		





